



REV	DESCRIPTION	APVD BY	DATE
2	MINOR UPD'S		16/04/15
1	UPD'D TO SHOP ORDER FROM FT-10572 GEN. DWG		6-1-15
0	FIRST ISSUE		----

REVISIONS

<b>CHASSIS:</b> INTERNATIONAL 4400 <b>PUMP:</b> HALE QMAX 1250 IGPM <b>TANK:</b> 1000 Imp. Gal. POLYPROPYLENE 1 - 20 Imp. GAL FOAM CELLS  <b>FOAM:</b> HYPRO FOAM 2001 PRO TANK PREMAX 140-D C.A.P.S.	<b>SUCTION:</b> 1 - 6" LEFT (ELEC MIV.) 1 - 6" RIGHT (ELEC MIV.) 1 - 6" REAR (5" PIPE, ELEC MIV.) 1 - 2 1/2" LEFT 1 - 2 1/2" RIGHT 1 - 4" TANK TO PUMP	<b>DISCHARGES:</b> 1 - 4" RIGHT 1 - 3" MONITOR 2L, 2R - 2 1/2" (RS FOAM) C.A.P.S. 1 - 2 1/2" RIGHT (FOAM) C.A.P.S.	2 - 1 1/2" CROSSLAYS (FOAM) C.A.P.S. 1 - 3" TANK FILL 1 - 1 1/2" FRONT TRASHLINE (FOAM) C.A.P.S.	<b>SIMONDS FIRE DEPARTMENT</b> TITLE: GENERAL ARRANGEMENT	
				JOB No. 18241 DRAWN BY J. O'LEARY DATE 6-1-15	
				METALFAB LTD. 847 CENTRAL ST. CENTREVILLE NB. CANADA E7K 2E8	
				DRAWING NO. FT-10677 REV 2	

-ALL ALUMINUM CONSTRUCTION - ALL DIMENSIONS ARE IN INCHES & APPROXIMATE